D03 · Industrial Automation & Robotics

03 · Vision systems & machine inspection

Supply Chain Reference Architecture v2.2 · mrsupplychain.ai

1 WHAT IT IS

Vision systems are machine-mounted imaging hardware (cameras, lighting, optics) paired with software (image acquisition, processing, decision logic) that automate inspection, measurement, identification, and guidance tasks. The deployment ranges from end-of-line quality gating (presence/absence, dimensional check, defect detection) to in-process control (feedback to equipment that prevents the defect from forming). The economic difference between the two deployments is enormous; the technical difference is where the data goes after the image is processed.

2 WHY IT MATTERS

Vision systems are one of the highest-ROI automation investments available to modern manufacturing — and one of the most consistently under-deployed because the dominant use case is end-of-line inspection rather than in-process control. **The asymmetry is enormous: a vision system deployed as end-of-line inspector detects the defect and counts the scrap; the same vision system deployed in-process with feedback to the equipment prevents the defect from forming in the first place**. The foundational text on machine vision applications quantifies the technical envelope **(Steger, Ulrich & Wiedemann, 2018 — peer-reviewed, "Machine Vision Algorithms and Applications", 2nd ed., Wiley-VCH)**, and industry data on deployed systems is consistent: **end-of-line vision deployments typically pay back capex in 18–30 months through scrap reduction and labor avoidance; in-process control deployments with feedback to equipment typically pay back in 6–12 months through defect prevention**. The 2–3x ROI gap is structural — the same camera, the same algorithm, the same operator, but radically different value depending on whether the system controls or merely counts.

3 HOW IT IS DONE

1. **Specify the inspection task before considering any camera — and force the question of whether the inspection should be in-process or end-of-line.** A defect detected at end-of-line is a part already made wrong; a defect detected in-process can be prevented. The case-design question is whether the upstream equipment can be controlled by the vision signal (close the loop) or only audited by it (open loop). Plants that default to end-of-line because it is easier to deploy capture roughly half the available value.
2. **Engineer lighting before optics, optics before camera, camera before software — in that order.** Most vision-system failures are lighting failures dressed up as algorithm failures. The image quality the camera captures depends on lighting (direction, intensity, wavelength, polarization), optics (lens focal length, depth of field, working distance), and camera (resolution, sensor type, shutter mode). A vision system that requires a sophisticated algorithm to compensate for poor lighting is a vision system that will fail when conditions change.
3. **Choose between rules-based and deep-learning algorithms by the failure-mode signature — not by which technology sounds more modern.** Rules-based vision (Cognex VisionPro classical, MVTec HALCON) is the right choice for well-defined inspections with clear geometric or photometric features (dimensional check, presence/absence, character recognition). Deep-learning vision (Cognex ViDi, Landing AI, Neurala) is the right choice for variable, naturally-occurring defects with high visual variability (surface defects, organic materials, complex assembly inspection). Plants that force deep learning on rules-based problems waste compute and training data; plants that force rules-based on deep-learning problems hit a ceiling at 80–85% detection.
4. **Close the control loop where the case permits — feed vision output back to the equipment that caused the defect.** A vision system measuring print quality at the end of a printing line tells you the print is bad; a vision system measuring print quality between print and cure that adjusts ink flow or temperature in real time prevents the bad print. Closing the loop requires (a) a controllable equipment parameter, (b) a defect signature predictive of the parameter drift, (c) integration between vision controller and equipment PLC. When all three exist, the in-process deployment is correct; when any is missing, the end-of-line deployment is the realistic option.
5. **Run an MSA (measurement system analysis) on the vision system as if it were a gauge — because it is one.** Vision systems drift like any measurement system: lens contamination, lighting degradation, software model drift on deep-learning

systems, environmental temperature change. The MSA discipline (gauge R&R, linearity study, bias study) applies as much to vision as to micrometers. Plants that skip MSA on vision systems run on faith that the camera is right; plants that include vision in their MSA program catch drift before it becomes a quality escape.

6. **Plan for the false-reject economics, not just the missed-defect economics.** A vision system that rejects 0.3% of good parts as defective on a high-volume line generates a significant scrap stream of its own. The acceptable false-reject rate depends on the part cost, the inspection consequence, and downstream capacity to triage rejects. Plants that optimize only the miss rate produce vision systems that catch every defect and scrap healthy parts; plants that optimize the joint miss-rate / false-reject-rate operating point produce systems that pay back economically.

WORKED EXAMPLE — ILLUSTRATIVE

An electronics contract manufacturer assembles surface-mount PCBs across 6 lines, with end-of-line AOI (automated optical inspection) detecting **8.2% defect rate ($6.1M annual rework cost; 14 operators dedicated to rework cells)**. The defects are dominated by three signatures: solder bridges (47% of defects), component misalignment (28%), and post-reflow tombstones (16%). Root-cause analysis shows all three signatures originate at specific upstream operations: solder bridges at paste deposition, misalignment at component placement, tombstones at reflow profile. The implementation: **migrate from end-of-line AOI to 3 in-process vision stations** with closed-loop feedback — (1) paste-deposition vision feeds height/volume back to the dispenser pressure controller, (2) placement vision verifies component orientation and triggers reject before reflow, (3) post-reflow thermal-vision feeds back to the reflow oven profile controller. End-of-line AOI is retained but as audit, not gate. Results at 12 months: **end-of-line defect rate 8.2% -> 1.4% (-83%), rework cost $6.1M -> $1.5M (-75%), 14 rework operators redeployed to value-added stations, vision system payback 9 months on a $740K total investment**. The same defects that were previously detected and reworked are now prevented at formation; the AOI camera that already existed contributed almost nothing to that result because it was looking after the fact.

IN PRACTICE

Specify in-process or end-of-line before considering hardware

End-of-line vision is a measurement system applied to finished product; in-process vision with feedback is a control system applied to the production process. Same hardware, categorically different deployments — and 2–3× ROI difference.

Engineer lighting before optics before camera before software

Most failed vision deployments fail at lighting **(Steger, Ulrich & Wiedemann, 2018 — peer-reviewed, Wiley-VCH)**. The camera with poor lighting solves nothing the deep-learning algorithm can recover; the camera with good lighting often makes the algorithm unnecessary. Light first.

Choose rules-based vs deep-learning by the failure-mode signature

Deterministic defects (presence/absence, dimensional, color) belong to rules-based vision; variable surface defects, organic-material inspection, and signatures-that-resist-specification belong to deep-learning. The wrong choice costs 5× the engineering effort for half the performance.

Plan for false-reject economics, not just missed-defect economics

A 99.5% defect-detection rate sounds excellent until the false-reject rate is 3% on a high-volume line — at which point the system rejects more good product than bad. MSA on vision is the gauge R&R discipline that surfaces this; without it the system passes the demo and fails in production.

WHAT YOU WOULD USE

MACHINE VISION PLATFORMS

Cognex (In-Sight, VisionPro, ViDi) — The dominant enterprise machine-vision platform with strong installed base across automotive, electronics, packaging, and life sciences; integrated hardware and software ecosystem with both rules-based and deep-learning capability **(Cognex — vendor)**.

Keyence (CV-X series, IV3, XG-X) / Omron (FH series) — Strong enterprise alternatives to Cognex with competitive technical capability and regional preference variation; particularly strong in Asia-Pacific markets and in operations with existing Keyence or Omron sensor footprint **(Keyence — vendor; Omron — vendor)**.

Landing AI / Neurala / MVTec HALCON — Deep-learning-specialized vision platforms for cases where rules-based vision cannot reach the required accuracy — surface defect detection, biological/organic material inspection, complex assembly verification **(Landing AI — vendor;**

MVTec — vendor).

OpenCV + Python + an industrial camera + in-house vision engineer — For operations with vision-engineering capability — open-source libraries (OpenCV, scikit-image, PyTorch) on standard industrial cameras (Basler, FLIR, Allied Vision). The lowest TCO and highest flexibility; requires the in-house engineering capability to be real and continuous.

4 SO WHAT

The vision system that counts defects at end-of-line is an expensive camera that quantifies scrap — vision without a control loop to the process prevents nothing. Specify whether the inspection should be in-process or end-of-line before considering hardware, engineer lighting before optics before camera before software, choose rules-based vs deep-learning by the failure-mode signature, close the control loop wherever the case permits, run MSA on vision systems as you would on any gauge, and plan for false-reject economics not just missed-defect economics. The 2–3x ROI gap between in-process control and end-of-line inspection is structural — and it lives entirely in whether the deployment was designed as control or merely as measurement.

From the SCRA v2.2 reference architecture · mrsupplychain.ai · © 2026 Ismael López · Mr. Supply Chain® México